CHITALDRUG DIVISION.

The 16th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 10th January 1898 for constructing a Tank near Chikmadare, Challakere taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1900.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M., Sundays and holidays excepted.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Tank near Chikmadare, Challakere taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork	C. yds.	11,060
Do	,,	72,550
Do breach	,,	43,028
Clearing silt	,,	6,209
Picking seat of bund	,,	4,196
Turfing	S. yds.	19,316
Grade stones	No.	34
Top width stones	,,	34
Gauge stone	,,	1
Tank No. stone	,,	1
Bench mark stone	,,	2
Clearing jungle	Lump sum.	
New stone work	C. yds.	6,878
Old stone work	,,	500
Total ..		
Sluice—		
Stone in chunam	C. ft.	2,012
Brick in chunam	,,	1,781
Plastering with chunam	S. yds.	9·98
Burnt stone slabs	S. ft.	200
Do dressed	,,	80
Cut stone	C. ft.	6
Lifting gear with shutters, &c., complete	No.	1
Plug with chain, &c., complete	No.	2
Total ..		
Weir—		
Earthwork	C. yds.	11,934
Brick in chunam	C. ft.	859
Slabs	S. ft.	160
Plastering	Sqr.	3·00
Apron	C. yds.	150
Total ..		..
Distribution—		
Irrigation channels	Lump sum.	

The 23rd December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 18th January 1898 for constructing a new Tank near Kalhalli, Chitaldrug taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1900.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Tank near Kalhalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a new Tank near Kalhalli village, Chitaldrug taluk.

Items of work.	*Per.*	*Quantity.*
Digging seat of bund	C. yds.	8,388
Earthwork to bund	,,	135,136
Rough stone work, new	,,	8,900
Turfing	Sqr.	2,137·20
Clearing jungle and shrubs	Lump sum.	
Removing silt in hallas	..	..
Bailing water	..	..
B. M. stones with bed slabs	No.	2
Date and R. No. stone	,,	1
Grade stones with bed slabs	,,	42
Top width stones	,,	42
Gauge stones with bed slabs	,,	2
Waste weir—		
Excavation through stony and gravelly soil	C. yds.	48·18
Rough stone new	,,	50
Turfing training bund	Sqr.	7·50
Sluice—		
Excavation through gravelly soil	C. yds.	20
Brick in mortar	C. ft.	1,182
Burnt stone slabs	S. ft.	182
Rough plastering	Sqrs	6·27
Plastering with mortar	,,	4·52
Fixing new gibbets	Lump sum.	
Sluice right—		
Excavation gravelly soil	C. yds.	20
Brick in mortar	C. ft.	1,182
Rough plastering	Sqrs.	6·27
Burnt stone slabs	S. ft.	182
Plastering with mortar	Sqrs.	4·52
Fixing new gibbets, &c.	Lump sum.	

The 14th December 1897.

It is here by notified for information of the public that the travellers' bangalo at Davangere, once closed for repairs as per Notification in *Mysore Gazette*, dated 25th March 1897, is now re-opened for travellers.

K. PRAHLADA RAO, *Offg. Executive Engineer.*